

HACCP plans for on-farm storage***Loading into store***

Task 18: Preparing store to receive grain (2)		
Hazard: Store may not be maintained in a state ready for efficient grain protection	Preventive measure: There must be no defective valves or seals. Sealed stores must be pressure tested. Pressure relief valve must be checked. Aeration system must be checked	Critical control point (CCP): Prior to loading commodity into store
Critical limit: Sealed stores must satisfy pressure test standard	Monitoring: Must be checked prior to filling & before fumigation	Corrective action: Seals must be replaced aeration equipment serviced
Verification/records: Equipment log should be maintained	Where to look: See sealed storage, silosealing, pressure testing, maintenance of pressure relief valves □ and aeration maintenance □	

[Click here for next task.](#)